



East End Fence Replacement

ADDENDUM NUMBER ONE

Prepared By: Portland Water District
Portland Water District
225 Douglass Street
PO Box 3553
Portland, ME 04104-3553

Addendum Date: March 17, 2025

225 Douglass Street
Phone: 207.774-5961

P.O. Box 3553
Fax: 207.761-8329

Portland, Maine 04104-3553
Web: www.pwd.org

Additional Information

Amend the scope as follows: Please refer to Scope of Services below. This hereby replaces Attachment 4 Scope of Services included in the original RFB.

Amend the bid due date as follows: Bids are now due Monday March 24th, 2025 by 2pm.

****Please sign and submit this addendum with bid.****

Submitting Firm Name	Address
By	Title
Signature of Person Bidding and Date	

--Addendum should be signed and submitted with bid--

**225 Douglass Street
Phone: 207.774-5961**

**P.O. Box 3553
Fax: 207.761-8329**

**Portland, Maine 04104-3553
Web: www.pwd.org**

2025- EEWWTF Fence Replacement

6' High Black Chain Link Fence Specifications:

- All fence framework, wire, and hardware to be PVC coated black.
- Line posts to be 2.5" OD ss 40 weight pipe, spaced 10' on center.
- Terminal posts to be 3" OD ss 40 weight pipe.
- Top and bottom rails to be 1 5/8" ss 40 weight pipe.
- Chain link fabric to be 6' high x 2" mesh x 8FB. (9 ga core, 8 ga finish 2B)
- All ties to be 9-gauge steel.
- System to include 3 strands of black barb-wire.
- All posts to be set in a 12" round x 42" deep 3,000 psi concrete footing.

Fence Scope:

- Approximately 4,900lf of fence removal.
- Approximately 4,900lf of new 6' high black chain link fence to be installed.
- (2) New 6' high x 16' wide double drive gates.
- (1) New 6' high x 4' wide single swing gate.
- (1) New 6' high x 4' wide single swing gate with panic bar.

Alternate 1:

- All line posts to be driven 4' deep instead of concrete footings. Terminal posts to still be concreted.